
C-106	E-117	A-107	D-106	P-116A/B	P-117A/B	A-108
Naphtha splitter ID 3.1 m x 29.5 m T/T DESIGN 3.5 barg / 185 C; CA 3 mm 38 valve trays, feed tray 21 MAT'L CS	Splitter reboiler (MP steam) 225 m2; 1 shell(s) DESIGN 5 / 13 barg / 280 C; CA 3 mm DUTY 6.83 MW SHELL: Naphtha / TUBE: MP steam MAT'L CS	Splitter overhead condenser 881 m2 bare; 2 bay(s) 6 m x 12 m, 4 fans DESIGN 9.7 barg / 115 C DUTY 9.63 MW; 4 x 30 kW fans MAT'L CS tubes, Al fins (A-101: CS + inlet ferrules, Ti optional)	Splitter reflux drum ID 2.7 m x 8.5 m T/T DESIGN 3.5 barg / 120 C; CA 3 mm MAT'L CS	Splitter reflux / LN RATED 146 m3/h @ 111 m, dP 7 bar MOTOR 55 kW; API 682 Plan 11/52 DES. T 80 C; MAT'L S-6 (CS/12Cr)	Heavy naphtha product RATED 142 m3/h @ 98 m, dP 6 bar MOTOR 45 kW; API 682 Plan 11/52 DES. T 185 C; MAT'L S-6 (CS/12Cr)	Heavy naphtha product cooler 401 m2 bare; 1 bay(s) 6 m x 12 m, 2 fans DESIGN 9.7 barg / 185 C DUTY 5.81 MW; 2 x 30 kW fans MAT'L CS tubes, Al fins (A-101: CS + inlet ferrules, Ti optional)



NOTES

1. C-106 pressure controlled by flooded condenser (PV-1100 on A-107 outlet) with D-106 balance line.
2. E-117 vertical thermosyphon reboiler, MP steam; condensate via steam trap set to condensate header.
3. Light naphtha to isomerisation, heavy naphtha to NHT/reformer (A-108 product cooler).
4. Line numbers: <NPS>-<fluid>-<area>-<seq>-<class>-<insulation> per CONVENTIONS; see line list CFU-000-PI-LL-001.
5. All vents / drains 3/4" min. with blind or cap; HPV/LPD to piping specification. Valve sizes = line size UNO.
6. Instrument tags per ISA-5.1; index CFU-000-IC-IDX-001. SIS functions per SRS (SIF tags shown in interlocks).

REV	DATE	DESCRIPTION
A	2026-10-02	Issued for review (FEED)

GENERIC REFINERY - GULF COAST

100 KBPSD CRUDE & VACUUM DISTILLATION UNIT

PIPING & INSTRUMENT DIAGRAM

NAPHTHA SPLITTER C-106

DISCIPLINE	STAGE	SCALE	SHEET
PROCESS	FEED	NTS	12 OF 17

DRAWN	CHECKED	APPROVED	DATE
CLAUDE CODE	-	-	2026-10-02

DRAWING NUMBER

CFU-100-PR-PID-011

REV **A**